

Digital Projection M Vision LED 1000 1080p



Brief Introduction

Beta 2.5

The M Vision LED 1000 1080p LED BrilliantColor DLP has 1000 Ansi-Lumen a contrast of 10000:1 and a HDTV 1920 x 1080 resolution. It is an LED projector with 60000 hours of light life, which is over 41.1 years with a daily viewing of 4 hours. The projector also offers a lens shift function for flexible projection adjustment without loss of quality. 1000 Ansi lumens ensure that an image width of 321 cm is also possible. However, if room light is available, the picture should be a maximum of 214 cm wide. Playing 1080P is also no problem for the projector. At just 30 decibels, the device is one of the quieter projectors. The model was built by Digital Projection in 2013 and is no longer current.

Display Type

1 x 0,95" DDR DLP Chip
HDTV 16/9 Ti Digital Light Processing Chip

Ansi-Lumen

1000 444 Lux (bei 200 cm Screen)

Contrast

10000:1 full on/off 10000:1 full on/off

Black Level

0,1000 min. Lumen 0,044 min. Lumen

Lens shift

Vert.: +/-60% Hori.: +/-15%

Resolution

HDTV 1920 x 1080
2.073.600 Pixel

Video Modes

PAL, SECAM, NTSC, HDTV 720p, 1080i, 1080p EDTV 480p, 576p

Disc Recognition

DVD | HD Blu-ray | 3D Blu-ray | 4K UHD Blu-ray

Application

Homeciname | Small screen width, rooms with very little ambient light below 100 lumens.

Light Source

LED

Light Life

Article Nr.: 109-683
60000 h.

Operating Costs

0,00 € LED

Focus

Manual

Zoom

Manual

Objective

optional

Throw Ratio

optional

Audio

Nein

Connections

2 x HDMI 1.3 in
D-sub 15 pin in
YUV in
S-Video in
Cinch Video in
RS232C Din 9 pin
2 x 12V Trigger out

Ceiling Mounting

Yes, is possible.

Power

330W

Size WxHxD


447 x 182 x 418 mm (17,6"x7,2"x16,5") 34,01 L/dm³

Operating Noise


30dB

Weight

15,00 kg / 33,07 lbs.



Keystone -
 Illumination 87%
 Frequenz V-sync: 43-85 Hz
 Range max.: 165 MHz
 Foot-Lamberts 41 fL / max. 321 cm screen width
 140 cd/m²
 Features
 ■ Full HD 1080P compatible
 ■ Lens shift Funktion
 ■ Gamma correction
 ■ BrilliantColor™
 ■ Lan network compatible.
 ■ Overscan adjustable
 ■ 5-segment colour wheel
 Screen Mirroring
 Optional only Chromecast / Fire TV / Apple TV / Mi Box Ads



Optional Lenses					
Name	Ratio	Distance	Shift V	Shift H	Zoom
Zoom Optional Lenses					
110-172	1.85-2.4:1	3.7-4.8 m	+/-60%	+/-15%	Manual
110-157	1.56-1.86:1	3.1-3.7 m	+/-60%	+/-15%	Manual
Fix Optional Lenses					
110-171	0.73:1	1.5 m	0.00% Fix		No Zoom

Status 2013 Discontinued (EOL) // Last update of the data: 2025-03-03
 Data Created: 2013-06-25 16:21:24

More Details



HCinema

<https://www.projector-database.com/pro/digitalprojectionmvisioncineled1000-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice.
 HCinema is not responsible for any errors or omissions contained in product descriptions.