


Digital Projection Titan Super Quad WUXGA 3D

DIGITAL PROJECTION TITAN SUPER



Brief Introduction

Beta 2.5

The Titan Super Quad WUXGA 3D DLP has 20000 Ansi-Lumen, a contrast of 2000:1 and a WUXGA 1920 x 1200 resolution. With the lens shift function, the projector can be positioned very freely. An image width of up to 1437 cm is possible, if the image width is smaller (we recommend max. 958 cm), rooms with residual light are also no problem. If the image is still too small, the integrated edge blending software can help to project a large image with additional projectors. The projector can also play 1080P and 3D without any problems. The model was built by Digital Projection in 2015 and is no longer current, but is still very popular in our projector database.



3 x 0,96" DLP Chip
WUXGA 16/9 Ti Digital Light Processing Chip

Display Type

Ansi-Lumen

20000

Contrast

2000:1 full on/off

Black Level

10,0000 min. Lumen

Lens shift

Vert.: +56,7% -45% Hori.: +/-18,8%

Resolution

WUXGA 1920 x 1200

Video Modes

2.304.000 Pixel

WUXGA 1920 x 1200 compressed

3D Compatibility

Pal, SECAM, NTSC, HDTV 720p, 1080i, 1080p, 3D, EDTV 480p, 576p

Frame-Packing (Full HD 3D) | Side-by-Side | Top-and-Bottom

Frame Sequential (3D Ready)

Application

Event | Very large screen width and rooms with plenty of light and shaded daylight.

Light Source

4 x 465W Lamp

Light Life

Article Nr.: 113-628 / 113-714 / 113-715

1500 h.

Operating Costs

-

Focus

Powered

Zoom

Powered

Objective

optional

Throw Ratio

optional

Audio

Nein

Connections

HDMI 1.3 in

DVI-D in

D-sub 15 pin in

5 x BNC RGBHV in

BNC Video in

3G-SDI in

USB Typ B

RS232C Din 9 pin in

RJ45 in

3D Sync in und out

Ceiling Mounting

Yes, is possible.

Power


2400W

Size WxHxD


585 x 258 x 688 mm (23"x10,2"x27,1") 103,84 L/dm³

Operating Noise

48dB



Weight	39,00 kg / 85,98 lbs.
Keystone	-
Illumination	-
Frequenz	H-sync: 15-100 kHz V-sync: 24-85 Hz Range max.: 170 MHz
Foot-Lamberts	826 fL / max. 1437 cm screen width 2830 cd/m²
Features	Real Full HD 3D Full HD 1080P compatible Lens shift Funktion Eco Mode Edge Blending Picture-in-Picture Lan network compatible.
Screen Mirroring	-



Optional accessories

	Einzel Lampe Ruby	Ruby-LMP23671	325,33 €
	4-er Pack Lampe inkl. Luftfilter Original	113-715	EOL €
	Einzel Lampe inkl. Luftfilter Original	113-628	1.190,30 €
	Doppel Lampe inkl. Luftfilter Original	113-714	2.472,31 €
	Deckenhalterung	HeavyDuty	378,28 €

Optional Lenses

Name	Ratio	Distance	Shift V	Shift H	Zoom
Zoom Optional Lenses					
109-236	1.16-1.49:1	2.3-3 m	+/-40.8%	+/-18.8%	Powered
109-235	6.92-10.36:1	13.8-20.7 m	56.7-45%	+/-18.8%	Powered
105-613	4.16-6.96:1	8.3-13.9 m	68.5-45%	+/-18.8%	
105-612	2.56-4.16:1	5.1-8.3 m	56.7-45%	+/-18.8%	
105-610	1.87-2.56:1	3.7-5.1 m	56.7-45%	+/-18.8%	Powered
105-610	1.39-1.87:1	2.8-3.7 m	56.7-45%	+/-18.8%	Powered
Fix Optional Lenses					
105-609	1.12:1	2.2 m	68.5-50%	+/-18.8%	No Zoom
105-608	1.12:1	2.2 m	56.7-45%	+/-18.8%	
105-607	0.67:1	1.3 m	+/-10.8%	+/-4.4%	No Zoom

Status 2015 Discontinued (EOL) // Last update of the data: 2025-03-03
 Data Created: 2015-08-14 13:02:55

More Details




<https://www.projector-database.com/pro/digitalprojectiontitansuperauadwuxga3d-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.