

Digital Projection TITAN WUXGA 330 L



Brief Introduction

Beta 2.5

A brief introduction to the TITAN WUXGA 330 L: The Digital Projection stationary 3D DLP projector offers 7000 Ansi lumens, a contrast of 2000:1 and a WUXGA 1920 x 1200 resolution. The integrated lens shift gives freedom when positioning the projector. Thanks to the brightness of 7000 Ansi lumens, an image width of 850 cm is possible. The projector can also handle slightly brighter rooms with a narrower image width (we recommend a maximum of 567 cm). Video signals 1080P and 3D are also no problem for the projector. The model was built by Digital Projection in 2011 and is no longer current.

Display Type



3 x 0,97" 12 Grad DLP Chip

WUXGA 16/9 Ti Digital Light Processing Chip

Ansi-Lumen

7000

3111 Lux (bei 200 cm Screen)

Contrast

2000:1 full on/off

2000:1 full on/off

Black Level

3,5000 min. Lumen

1,557 min. Lumen

Lens shift

Vert.: +70% -50% Hori.: +/-18,7%

Resolution

WUXGA 1920 x 1200

2.304.000 Pixel

Video Modes

Pal, SECAM, NTSC, HDTV 720p, 1080i, 1080p, 3D, EDTV 480p, 576p

3D Compatibility

Frame-Packing (Full HD 3D) | Side-by-Side | Top-and-Bottom
Frame Sequential (3D Ready)

Application

Stationary | Permanent installation in the training room and meeting room as well as the conference room.

Very large screen width and rooms with plenty of light and shaded daylight.

Light Source

330W Lamp

Article Nr.: 109-319

Light Life

1500 h. 3000 h. in Eco Mode

Operating Costs

-

Focus

Powered

Zoom

Powered

Objective

optional

Throw Ratio

optional

Audio

Nein

HDMI 1.4

DVI in

D-sub 15 pin in

Connections

5 x BNC RGBHV in

YUV über BNC in

BNC Video in

RJ45 in

RS232C

Ceiling Mounting

Yes, is possible.

Power


950W

Size WxHxD


543,5 x 253,5 x 645,4 mm (21,4"x10"x25,4") 88,61 L/dm³

Operating Noise

45dB



Weight	31,00 kg / 68,34 lbs.
Keystone	-
Illumination	87%
Frequenz	H-sync: 15-100 kHz V-sync: 24-85 Hz
Foot-Lamberts	289 fL / max. 850 cm screen width 990 cd/m²
Features	Real Full HD 3D Full HD 1080P compatible Lens shift Funktion Freeze Eco Mode Gamma correction Password protection Wi-Fi network compatible. Lan network compatible.
Screen Mirroring	-



Optional accessories

	Einzel Lampe Ruby	Ruby-LMP20266	321,57 €
	Einzel Lampe inkl. Luftfilter Original	111-258 / 109-319	EOL €
	Deckenhalterung Länge 225 mm	Halterung45	85,80 €

Optional Lenses

Name	Ratio	Distance	Shift V	Shift H	Zoom
Zoom Optional Lenses					
109-236	1.16-1.87:1	2.3-3.7 m	70-50%	+/-18.75%	Powered
109-235	6.92-10.36:1	13.8-20.7 m	70-50%	+/-18.75%	Powered
105-613	4.16-6.96:1	8.3-13.9 m	70-50%	+/-18.75%	
105-612	2.56-4.16:1	5.1-8.3 m	70-50%	+/-18.75%	Powered
105-611	1.87-2.56:1	3.7-5.1 m	70-50%	+/-18.75%	Powered
105-610	1.39-1.87:1	2.8-3.7 m	70-50%	+/-18.75%	Powered
Fix Optional Lenses					
105-609	1.12:1	2.2 m	70-50%	+/-18.75%	
105-608	1.12:1	2.2 m	70-50%	+/-18.75%	No Zoom
105-607	0.67:1	1.3 m	+/-10%	+/-10%	No Zoom

Status 2011 Discontinued (EOL) // Last update of the data: 2025-03-03
 Data Created: 2012-11-08 16:03:28

More Details



HCinema
<https://www.projector-database.com/pro/digitalprojectiontitanwuxga330l-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.