

Liesegang Piccadilly plus

LIESEGGANG PICCADILLY PLUS



Brief Introduction

Beta 2.5

A brief introduction to the Piccadilly plus: The Liesegang standard portable DLP projector offers 1500 Ansi lumens, a contrast of 1500:1 and an SVGA 800 x 600 resolution. An image width of up to 337 cm is possible. However, the image should be smaller in room light. We recommend max. 225 cm. The model was built by Liesegang in 2004 and is no longer current. It should also be noted that, unfortunately, there are no more replacement lamps for the projector, neither originals nor replicas.

Display Type

1 x 0,55" DLP Chip
SVGA 4/3 Ti Digital Light Processing Chip

Ansi-Lumen

1500

500 Lux (bei 200 cm Screen)

Contrast

1500:1 full on/off

1500:1 full on/off

Black Level

1,0000 min. Lumen

0,334 min. Lumen

Offset

Resolution

SVGA 800 x 600

480.000 Pixel

Video Modes

XGA 1024x768 compressed

Pal, Secam, NTSC,HDTV

Application

Standard-Portabel | External training and company presentations, as well as product presentations.

Small screen width, rooms with very little ambient light below 100 lumens.

Light Source

200W P-VIP Lamp

Articel Nr.: ZU 0216 04 4010

Light Life

2000 h.

Operating Costs

-

Focus

Manual

Zoom

Manual 1,14

Objective

F=2,6 f=19,3-22 mm

Throw Ratio


1,73-1,97:1

Audio

1 x 1W

Connections

DVI-I in
Cinch Video in
S-Video in
Mini Jack in
USB





Ceiling Mounting
Power
Size WxHxD
Operating Noise

Yes
250W / 10W standby
280 x 97 x 205 mm (11"x3,8"x8,1") 5,57 L/dm³
32dB

Weight
Keystone
Illumination

2,00 kg / 4,41 lbs.
Vert.: +/-15°
80%

Frequenz

H-sync: 15-70 kHz
V-sync: 43-85 Hz

Foot-Lamberts

46 fL / max. 337 cm screen width
158 cd/m²

Features

- Freeze
- Kensington Slot
- Gamma correction
- Picture-in-Picture
- 16 times digital Zoom
- De-interlacer

In Test
Status

-
2004 Discontinued (EOL) // Last update of the data: 2023-08-04

Data



More Details



HCinema

<https://www.projector-database.com/pro/liesegangpiccadillyplus-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.