

projectiondesign F22 720p

PROJECTIONDESIGN F22 720P



Brief Introduction
Beta 2.5

A brief introduction to the projectiondesign F22 720p. The standard portable DLP projector has an HDTV 1280 x 720 resolution and a contrast of 2500:1. The projector can be positioned very freely using the lens shift function. Thanks to the brightness of 1200 Ansi lumens, a picture width of 352 cm is possible. In room light, the image should be max. 235 cm wide. Even 1080P video signals are no problem for the projector. The projector is very quiet compared to others with 24 decibels of operating noise. The model was built by projectiondesign in 2009 and is no longer current.

Display Type

1 x DLP Chip
HDTV 16/9 Ti Digital Light Processing Chip

Ansi-Lumen

1200

533 Lux (bei 200 cm Screen)

Contrast

2500:1 full on/off

2500:1 full on/off

Black Level

0,4800 min. Lumen

0,213 min. Lumen

Lens shift

Vert.: +50% -0%

Resolution

HDTV 1280 x 720

Video Modes

921.600 Pixel
HDTV 1920 x 1080 compressed

Application

PAL, SECAM, NTSC, HDTV 720p, 1080i, 1080p EDTV 480p, 576p
Standard-Portabel | External training and company presentations, as well as product presentations.

Light Source

Small screen width, rooms with very little ambient light below 100 lumens.

Light Life

220W UHP Lamp
3000 h. 2250 h. in high power mode

Operating Costs

-

Focus

Manual

Zoom

Manual 1,25

Objective

-

Throw Ratio

1,95-2,43:1

Audio


1 x 2W

Connections

HDMI 1.3
DVI-I mit HDCP in
D-sub 15pin in
S-Video in
Cinch Video in
RS232C Din 9pin in
12V Trigger out

Ceiling Mounting
Power


Yes
290W



Size WxHxD 278 x 94 x 234 mm (10,9"x3,7"x9,2") 6,11 L/dm³
Operating Noise 24dB

Weight 3,00 kg / 6,61 lbs.
Keystone Vert.: +/-30°
Hori.: +/-15°
Illumination -
Frequenz H-sync: 15-150 kHz
V-sync: 48-190 Hz
Range max.: 205 MHz
Foot-Lamberts 50 fL / max. 352 cm screen width
171 cd/m²

- Full HD 1080P compatible
- Lens shift Funktion
- Eco Mode
- Kensington Slot
- Gamma correction
- 24/7 continuous operation capable
- Password protection
- BrilliantColor™
- Remote control with laser pointer und mouse control
- Lan network compatible.
- Faroudja De-Interlacer.
- Programmable timer.
- Various colour wheels:
 - RGBRGB – visualisation & simulationoperating mRGBCMY – graphics display
 - mRGBCYW – high brightness display



Optional Lenses						
Name	Ratio	Distance	Shift V	Shift H	Zoom	
Zoom Optional Lenses						
long throw zoom	3-4.65:1	6-9.3 m	50%		Manual	
Fix Optional Lenses						
Wide angle 1:1	1.1:1	2.2 m	40%		No Zoom	
ultra wide angle0.80:1	0.87:1	1.7 m	0.0% Fix		No Zoom	
Status	2009 Discontinued (EOL) // Last update of the data: 2023-08-04					

Data



More Details



HCinema

<https://www.projector-database.com/pro/projectiondesignef22720p-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.