


Vivitek RH46623



VIVITEK RH46623



Brief Introduction

Beta 2.5

A brief introduction to the Vivitek RH46623. The stationary DLP laser projector has a HDTV 1920 x 1080 resolution and a contrast of 20000:1. The lifespan is 20000 hours due to the laser, which is over 13.7 years with a daily viewing time of 4 hours. Including a lens shift and keystone correction function, which provides freedom during installation. Thanks to the brightness of 6000 Ansi lumens, a picture width of 787 cm is possible. The projector can also handle slightly brighter rooms with a narrower picture width (we recommend max. 525 cm). With the HDMI MHL port, the smartphone image can be transmitted to the projector in Full HD at 60 Hz by screen mirroring and the smartphone is charged at the same time. It is also Full HD 1080P and 3D compatible. The model was built by Vivitek in 2017 and is no longer current.



1 x 0,65" DMD DLP Chip
HDTV 16/9 Ti Digital Light Processing Chip

Display Type

Ansi-Lumen
Contrast
Black Level
Lens shift

Projector
6000
20000:1 full on/off
0,3000 min. Lumen
Vert.: +12% -0% Hori.: +/-5%

Screen
2667 Lux (bei 200 cm Screen)
20000:1 full on/off
0,133 min. Lumen

Resolution

HDTV 1920 x 1080
2.073.600 Pixel
WUXGA 1920 x 1200 compressed

Video Modes

Pal, SECAM, NTSC, HDTV 720p, 1080i, 1080p, 3D, EDTV 480p, 576p

3D Compatibility

Frame-Packing (Full HD 3D) | Side-by-Side | Top-and-Bottom
Frame Sequential (3D Ready)

Application

Stationary | Permanent installation in the training room and meeting room as well as the conference room.

Light Source

Very large screen width and rooms with plenty of light and shaded daylight.

Light Life

Laser
20000 h.

Operating Costs

0,00 € Laser

Focus

Manual

Zoom

Manual 1,65

Objective

F=2,45-3,13 f=17,23-27,9 mm

Throw Ratio

1,15-1,9:1

Audio

2 x 5W

Connections


3x HDMI (MHL) in
D-sub 15pin in und out
Cinch Video in
Cinch Stereo in
Mini Jack Audio in und out
USB in
RS232C Din 9 pin in
RJ45 in
1x Mikrofon
1x 3D Sync Out

Ceiling Mounting


Yes

Power

430 / 350W in Eco Mode



Size WxHxD	350 x 167 x 450 mm (13,8"x6,6"x17,7") 26,3 L/dm³
Operating Noise	38 / 36 dB in Eco Mode
Weight	10,70 kg / 23,59 lbs.
Keystone	Vert.: +/-30°
Illumination	Hori.: +/-30°
	-
Frequenz	H-sync: 15,31-91,4 kHz
	V-sync: 24-120 Hz
Foot-Lamberts	248 fL / max. 787 cm screen width
	850 cd/m²
Features	■ Real Full HD 3D
	■ Full HD 1080P compatible
	■ Lens shift Funktion
	■ Eco Mode
	■ BrilliantColor™
Status Data	■ Lan network compatible.
	■ Crestron®-Software compatible.
	■ 2017 Discontinued (EOL) // Last update of the data: 2023-09-20



More Details



HCinema

<https://www.projector-database.com/pro/vivitekrh46623-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.